

V-E-1



TOWN AND VILLAGE OF HARRISON
DEPARTMENT OF PUBLIC WORKS



October 8, 2013

Mayor Ron Belmont and
Members of the Village Board
Village of Harrison
1 Heineman Place
Harrison, New York 10528

Re: Change Orders #1 and #2 (Revised)
Installation of a Concrete Pad at the Recycling Center
Gleason Place Utility Garage

Dear Mayor Belmont and Members of the Village Board:

Village Board authorization is requested for Change Orders #1 and #2 to contract with Coppola Paving and Landscaping Corp. at a cost not to exceed \$50,340.00. The work tasks and associated costs related to these change orders are summarized below:

Change Order #1 – During the performance of concrete work it was noted that there were several additional locations that were badly deteriorated. This necessitated the placement of an additional 1,490 square feet of concrete. Change Order #1 provides additional compensation in the amount of \$23,840.00 to the contractor to furnish all labor, materials and equipment necessary for the placement of additional concrete.

Change Order #2 – A 6,610 square foot area of existing asphalt at the south end of the facility is badly deteriorated and requires replacement. Change Order #2 provides additional compensation to the contractor in the amount of \$26,500.00 to furnish all labor, materials and equipment necessary to place NYSDOT Type 3 HD Binder Asphalt in the affected area.

Copies of the proposals are attached for your information and review.

Further authorization is requested for the Law Department to increase the upset limit for this contract by \$50,340.00 from \$67,400.00 to a revised contract amount of \$117,740.00.

Finally, funding for this change order is available in the following Capital Accounts: 13HW09 and 13HW11.

Respectfully submitted,

Anthony P. Robinson
Commissioner of Public Works

APR/fmb

Attachments

Cc: Purchasing Department
Law Department



COPPOLA PAVING & LANDSCAPING CORP.

General Contractors & Builders

Asphalt • Cement • Excavation • Masonry • Sitework • Tennis Courts

Main Office:

3830 BOSTON ROAD • BRONX, NY 10475
718-325-8815 • 914-921-8815 • FAX 718-325-9305

October 3, 2013

Town of Harrison/Village of Harrison
Alfred F. Sullia, Jr. Municipal Building
1 Heineman Place
Harrison, NY 10528

Attention: Anthony P. Robinson, Commissioner of Public Works
Re: Installation of a Concrete Pad at the Recycling Center at Gleason Place Utility Garage.
Change Order Proposal # 1 for An Additional 1,490 Square Feet of Slab Beyond the
Contract Amount

Gentlemen,


Coppola Paving and Landscaping Corporation hereby proposes to furnish and install an additional 1,490 square feet of typical reinforced concrete slab construction as per your direction for location and plan dimensions, increasing the amount to be installed to 5,390 square feet in total.

We propose the unit price for this work to be \$16 per square foot. Therefore, the additional amount we are proposing for this additional work is $1,490 \text{ SF} \times \$16/\text{SF} = \$23,840.00$.

The new contract amount will therefore, become the original contract amount of \$67,400 plus the \$23,840.00 for a total revised contract amount of \$91,240.00.

Please issue a change for the above mentioned amount.

Very Truly Yours,
Coppola Paving and Landscaping Corporation


Richard S. Angus, PE
Senior Engineer

cc EC, PG.



COPPOLA PAVING & LANDSCAPING CORP.

General Contractors & Builders

Asphalt • Cement • Excavation • Masonry • Sitework • Tennis Courts

Main Office:

3830 BOSTON ROAD • BRONX, NY 10475
718-325-8815 • 914-921-8815 • FAX 718-325-9305

October 9, 2013

Town of Harrison/Village of Harrison
Alfred F. Sulia Jr. Municipal Building
1 Heineman Place
Harrison, NY 10528

Attention: Anthony P. Robinson, Commissioner of Public Works
Re: Installation of a Concrete Pad at the Recycling Center at Gleason Place Utility Garage
Change Order Proposal # 2 Additional Work for Heavy Duty Asphalt Repairs at Town
Garage

Gentlemen,

Coppola Paving and Landscaping Corporation hereby proposes to furnish and install NYSDOT Type 3 HD Binder Asphalt as described below, in the approximate area behind the garage as marked out during the walk through held on 10-4-13:

- Fill existing low spots with NYSDOT Type 3 HD Binder Asphalt and compact to level out the area.
- Mill all ends/edges of existing areas to meet the existing grades smoothly.
- Install approximately 2" to 3" of NYSDOT Type 3 HD Binder Asphalt and compact. Apply hot (asphaltic cement) AC 20 at all edges to prevent chaffing.

Areas approximately 98'x35' and 53' x 60' = 5610 SF +/- @ approx 3" thick = 132 tons +/-

Please note that this proposal assumes the town personnel will move the existing plows and stored equipment to allow Coppola to gain access to the areas. Our estimate includes 1 full crew day; equipment moves, milling edges, preparatory work and paving operations.

Lump Sum Proposal:

\$26,500

Very Truly Yours,
Coppola Paving and Landscaping Corporation


Richard S. Angus, PE
Senior Engineer