

HARRISON ENGINEERING DEPARTMENT

Town/Village of Harrison
Alfred F. Sulla, Jr. Municipal Building
1 Heineman Place
Harrison, New York 10528

Michael J. Amodeo, P.E., CFM
Town/Village Engineer



August 10, 2022

E-21

Supervisor Richard Dionisio and
Members of the Town Board
Town of Harrison
1 Heineman Place
Harrison, New York 10528

Re: West Street Drainage Project

Dear Supervisor Dionisio and Members of the Town Board:

Town Board authorization is requested to increase the Purchase Order # 421648 amount with ELQ Industries, Inc by \$130,000 for the drainage system installation within West Street.

Town Board previously provided authorization for the proposed contract amount of \$575,000 at the July 2022 Town Board meeting. Funding in the amount of \$445,000 was available at the time. We are requesting the remaining proposal amount for the project completion.

The scope of services is detailed in the attached proposal.

Funding in the amount \$130,000.00 is available in the Engineering Special Services Budget Line account # 001-1440-100-0407.

Further, authorization is requested for the Purchasing Department to increase the Purchase Order # 4221648 to ELQ Industries to an amount of \$575,000.00.

Respectfully submitted,

Michael J. Amodeo, PE, CFM
Town/Village Engineer

MJA/mep

Attachments



07/06/2022 14:24
 220705 West Street Drainage - Harrison
 *** Lony Silva

| | | BID TOTALS | | | | |
|-----------|---|--------------|-----------|-------|------------|--------------|
| Biditem | Description | Status - Rnd | Quantity | Units | Unit Price | Bid Total |
| 10 | General Conditions | | 1.000 | LS | 3,139.46 | 3,139.46 |
| 20 | Mobilization/Demobilization | | 1.000 | LS | 3,837.60 | 3,837.60 |
| 30 | Silt Fence | | 560.000 | LF | 11.16 | 6,249.60 |
| 40 | Inlet Protection | | 5.000 | EA | 206.30 | 1,031.50 |
| 50 | Saw Cut Pavement | | 910.000 | LF | 3.73 | 3,394.30 |
| 60 | Remove/Replace Asphalt Curb | | 45.000 | LF | 15.12 | 680.40 |
| 70 | Remove/Reinstall Stone Curb | | 163.000 | LF | 61.95 | 10,097.85 |
| 80 | Remove/Reinstall Stone Driveway Apron | | 73.000 | SF | 75.92 | 5,542.16 |
| 90 | Remove/Dispose of Existing Catch Basins | | 3.000 | EA | 269.87 | 809.61 |
| 100 | Remove/Dispose of Existing Drain Pipe | | 329.000 | LF | 4.92 | 1,618.68 |
| 110 | F&I 15" HDPE Pipe W/Backfill | | 135.000 | LF | 181.54 | 24,507.90 |
| 120 | F&I 24" HDPE Pipe w/Backfill | | 612.000 | LF | 240.63 | 147,265.56 |
| 130 | Connect Existing 12" Drain to New Catch Basin | | 1.000 | EA | 613.96 | 613.96 |
| 140 | F&I New Catch Basins W/Casting | | 1.000 | EA | 7,682.00 | 7,682.00 |
| 150 | F&I New Drain Inlet W/Casting | | 3.000 | EA | 9,879.25 | 29,637.75 |
| 160 | F&I New Drain Manhole W/Casting | | 4.000 | EA | 9,092.44 | 36,369.76 |
| 170 | Asphalt Restoration Road | | 2,857.000 | SF | 13.33 | 38,083.81 |
| 180 | Asphalt Restoration Driveways | | 446.000 | SF | 9.93 | 4,428.78 |
| 190 | Topsoil Seed Disturbed Areas | | 5,121.000 | SF | 2.07 | 10,600.47 |
| 200 | Landscape Allowance (Trees/Shrubs) | | 1.000 | LS | 1,835.94 | 1,835.94 |
| 210 | Cut Opening/Repair Stone Wingwall | | 1.000 | LS | 3,780.50 | 3,780.50 |
| 220 | Fence Repair | | 20.000 | LF | 144.35 | 2,887.00 |
| 230 | MPT (Flagmen/Signs) | | 1.000 | LS | 49,220.63 | 49,220.63 |
| 240 | Road Plates | | 1.000 | LS | 12,030.90 | 12,030.90 |
| 250 | Pavement Markings | | 1.000 | LS | 2,570.32 | 2,570.32 |
| 260 | Trench Rock Removal Allowance | | 100.000 | CY | 357.73 | 35,773.00 |
| 270 | Test Pits | | 4.000 | EA | 2,773.97 | 11,095.88 |
| 280 | Lower 6" Main | | 2.000 | EA | 51,390.39 | 102,780.78 |
| 290 | Lower Water Services | | 3.000 | EA | 5,142.69 | 15,428.07 |
| Bid Total | | | | | | \$572,994.17 |